

REQUEST FOR INFORMATION #2

PELLSTON ATHLETIC COMPLEX

4/07/2021

REQUEST FOR INFORMATION:

- 1) Q: Per the RFI #1 in reference to answers 4 & 5, Addendum #2 shows the 4 lights in a different location than the existing lights are currently. Based on the plans and the answers in the RFI this means that four of the existing light poles are to be relocated to the new design locations in Addendum #2, is this correct?
A: Yes, Refer to Cooper Lighting Solutions drawings in Addendum #2.
- 2) Q: Does the long jump area at the north end of the football field get resurfaced or does it get relocated? If relocated, to what location?
A: Yes, location to be determined.
- 3) Q: The new fence to the south of the shot put and discus location requires trees to be removed and the area to be graded. Is there any topsoil/seeding/irrigation required for the disturbed areas and areas around the shot put and discus pads?
A: The shot put, and discus remains where they are, as we are not moving the practice field. No updating or improvements to the practice field in Addendum 1.
- 4) Q: Are the shot put & discus pads to be removed and replaced?
A: The shot put, and discus remain where they are, as we are not moving the practice field. No updating or improvements to the practice field in Addendum 1.
- 5) Q: Are we to include a new concrete pad for the pole-vault?
A: Yes.
- 6) Q: Are there any restrictions on working days or start/ end times?
A: No.
- 7) Q: Are the loudspeakers located on the press box to be removed and reinstalled or are we to include new speaker equipment?
A: Remove existing and then reinstall.
- 8) Q: At the location where the concrete retaining wall meets the bleachers, can a form be left in place? If so, what are the finish requirements?
A: Yes, form can be left in place. Epoxy paint form, color to match concrete.
- 9) Q: Per sheet A113, the countertops are labeled as "Introsul Sill". That is a product we (cabinet/ counter company) have never heard of. Can a product please be specified?
A: We will accept substitute submittals for installers standard cultured marble.